No picture available at this time.

Rig 169

Medium Duty (1500 HP)

General Description

Design	National 110UE
Drilling Depth Rating	16,000 ft.
Sub-Base Height	20 ft.
Sub-Base Type	Pyramid Desert Rambler
Camp Capacity	92 persons
Estimated Total Rig Move Loads	47

Drilling Equipment

Derrick	Pyramid, 142 ft. Static Hookload Capacity – 750,000 lbs. with 10 lines strung
Drawworks	National 110UE, 1,500 HP, 1-3/8 in. Drilling Line
Rotary table	Oilwell B, 27-1/2 in.
Top drive	N/A
Mud pumps	2 x National 10P130, 1300 HP
Solids control	Shale Shakers – 3 x Derrick Flo-line Plus Desander – Double Life V-310, 3 x 10 in. Desilter – Brandt SE-16, 16 x 4 in. Mud Cleaner – Double Life MC-416

Storage Capacities

Active Mud	1,592 bbls.
Reserve Mud	500 bbls.
Bulk Material	

Power Equipment

DC Generators	4 x Ross Hill 1400 SCR 5 x Kato 1301-685361111, 1,030 kW
AC	5 x Caterpillar D-398, 912 HP

BOP Equipment

Diverter	Hydril MSP, 500 psi., 29-1/2 in. (Shared)
21-1/4 in. system	Hydril MSP, 2,000 psi, 21-1/4 in. Superior U, 2,000 psi, 21-1/4 in.
13-5/8 in. system	Cameron U, 5,000 psi, 13-5/8 in. Hydril GK, 5,000 psi, 13-5/8 in.

Special Features

Mud pumps on trailer.