No picture available at this time

Rig 174

Heavy Duty (3000 HP)

General Description

Design	Pyramid
Drilling Depth Rating	30,000 ft.
Sub-Base Height	29 ft.
Sub-Base Type	Pyramid Slingshot
Camp Capacity	100 persons
Estimated Total Rig Move Loads	150

Drilling Equipment

Derrick	Pyramid, 152 ft. Static Hookload Capacity – 1,500,000 lbs. with 12 lines strung
Drawworks	Emsco C3, 3,000 HP; 1-1/2 in. drilling line
Rotary table	Con. Emsco Ind Drive, 37-1/2 in.
Top drive	Varco BJ IDS – 1
Mud pumps	3 x Emsco FB1600, 1,600 HP
Solids control	Shale Shakers – 3 x Derrick, Flo-line, Model 58 Desander – Harrisburg, 4 x 10 in. Desilter – Harrisburg, 20 x 4 in. Mud Cleaner – 2 x Harrisburg, MC-800

Storage Capacities

Active Mud	2,000 bbls
Reserve Mud	2,000 bbls
Bulk Material	

Power Equipment

DC	Ross Hill SCR 1400
Generators	5 x Kato 1050, 5,250 kW
AC	5 x Caterpillar D-399TA, 1,215 HP

BOP Equipment

Diverter	N/A
30 in system	Shaffer, 1,000 psi
26-3/4 in system	S&S Single & Double “U”, 3,000 psi
21-1/4 in. system	Hydril MSP, 2,000 psi
13-5/8 in. system	Hydril GK, 5,000 psi CIW U 2D, 10,000 psi

Special Features

Additional Equipment – 50 ton Crane, D8N Cat, 966E Forklift.